



SOMERSET ACADEMY

TEXAS

Football Drainage Project Bid Specifications

1. **Project Description** - This project involves the investigation, repair, and restoration of ground failure within the football field end zone and the surrounding multi-lane track facility. The initial failure area is located at the corner of the southernmost portion of the track, with impacts extending beyond the circular track to the southeast corner between the perimeter fence and the track.

2. **Scope of Work the Contractor** – The scope of work includes evaluation and rehabilitation of the drainage infrastructure serving the southeast section of the football field, located above the track. Work will consist of:

- Assessment of existing drainage conditions to determine the cause and extent of failure
- Identification of compromised or damaged drainage piping
- Repair or replacement of defective drainage components
- Sinkhole stabilization and subgrade repair
- Restoration of the track surface, field areas, and any other affected improvements
- Removal and lawful disposal of all excavated materials and construction debris generated by the work

The objective of this project is to restore structural stability, ensure proper drainage functionality, and return all affected areas to their original or improved condition.

3. **Standards and Quality Control** - All work shall be performed in accordance with applicable local codes, industry standards, and best practices. Materials shall be new and suitable for subsurface drainage applications. Compaction shall be sufficient to prevent settlement and surface failure.

4. **Site Protection and Safety** - Contractor shall protect adjacent facilities, including the track and field surface, from damage. Maintain safe access and conditions at all times. Contractor is responsible for compliance with all OSHA and local safety regulations.

5. **Schedule Work** - shall be completed within the timeframe specified in the bid documents. Contractor shall coordinate work to minimize disruption to athletic activities.

6. **Submittals Contractor** - shall submit a work plan and schedule prior to mobilization. Product data for drainage materials may be required upon request.

7. **Measurement and Payment**-Payment shall be made as listed on the RFCSP for all work described in this specification unless otherwise noted in the bid schedule. No additional compensation will be provided for incidental work necessary to complete the project.

8. **Warranty Contractor** - shall warrant workmanship and materials for a minimum period of one (1) year from date of final acceptance.